

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-097-21423-00-01  
Spot: SENWNWNW Sec/Twnshp/Rge: 17-28S-17W  
4828 feet from S Section Line, 4729 feet from E Section Line  
Lease Name: YOHN Well #: 1-17  
County: KIOWA Total Vertical Depth: 4880 feet

Operator License No.: 3842  
Op Name: LARSON ENGINEERING, INC. DBA LAR  
Address: 562 W STATE RD 4  
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4736		
PROD	5.5	4878	2585	WITH 185 SX CMT
SURF	8.625	511		WITH 260 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/22/2017 12:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP BOTTOM 50' ABOVE PERFS WITH HULLS. PLUG AT 1120' WITH 10 SX GEL & 50 SX CMT. PLUG AT 560' WITH 50 SX CMT. PLUG AT 40' TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/22/2017 2:15 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PUMP 80 SX CMT & 400# HULLS. TAG AT 4050'. 1ST PLUG AT 1120' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 540' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4752	4768		
4673	4678		
4194	4198		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_  
(TECHNICIAN)

RECEIVED  
JAN - 9 2018  
KCC DODGE CITY