

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-22722-00-00
Spot: SWNENW Sec/Twnshp/Rge: 7-8S-21W
990 feet from N Section Line, 1650 feet from W Section Line
Lease Name: KENYON Well #: 1
County: GRAHAM Total Vertical Depth: 3633 feet

Operator License No.: 30606

String Size Depth (ft) Pulled (ft) Comments

Op Name: MURFIN DRILLING CO., INC.

PROD 4.5 3628 120 SX

Address: 250 N WATER STE 300
WICHITA, KS 67202

SURF 8.625 217 140 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/29/2017 9:00 AM

Plug Co. License No.: 34059

Plug Co. Name: HURRICANE SERVICES, INC.

Proposal Rcvd. from: SHAWN

Company: MURFIN DRILLING CO., INC.

Phone: (785) 421-2103

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Port Collar at 1657" w/450 sx cement.
Perforations: 3467' - 3471' and 3628' - 3629'

Plugging Proposal Received By: MARVIN MILLS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 12/29/2017 12:30 PM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3511' and pumped 75 sx cement w/150 # hulls. Pulled tubing to 2784' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 1783' and pumped 165 sx cement. Good circulation of cement. Pulled tubing. Topped off casing with 35 sx cement. Tied on to backside and squeezed with 50 sx cement. Shut in pressure 100 psi.

GPS: 39.37703 -099.70901

Perfs:

Top	Bot	Thru	Comments
3628	3629		
3467	3471		

Remarks: HURRICANE CEMENT TICKET # 101100

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

JAN 16 2018

CONSERVATION DIVISION
WICHITA, KS

JAN 02 2018

JAN 02 2018

Form CP-2/3

INVOICED
FEB 03 2018