

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-20274-00-00
Spot: E2NWSWSW Sec/Twnshp/Rge: 12-10S-24W
990 feet from S Section Line, 430 feet from W Section Line
Lease Name: GANO SE UNIT Well #: 2-8
County: GRAHAM Total Vertical Depth: 4084 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4075		250 SX
SURF	8.625	190		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/05/2018 10:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.
Perforations: 3818' - 3822', 3848' - 3856', 3860' - 3872', 3890' - 3894', 3902' - 3908', 3916' - 3922', 3952' - 3958', 3972' - 3976', 3990' - 3996' and 4012' - 4018'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/05/2018 1:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perforations at 180', 1265', 2105' and 2600'. Ran tubing to 3920' and pumped 75 sx cement w/300 # hulls. Pulled tubing to 3228' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 2538' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 1534' and pumped 75 sx cement. Good circulation of cement. Tied on to backside and squeezed with 50 sx cement. Pressured to 100 psi. Hole standing full.

GPS: 39.19278 -099.95760

Perfs:


Top	Bot	Thru	Comments
4012	4018		
3990	3996		
3972	3976		
3952	3958		
3916	3922		
3902	3908		
3890	3894		
3860	3872		
3848	3856		
3818	3822		

INVOICE
FEB 08 2018

Remarks: HURRICANE TICKET # 100865

Plugged through: TBG

District: 04

Signed  (TECHNICIAN)

JAN 08 2018

Received
KANSAS CORPORATION COMMISSION

CM

JAN 08 2018

JAN 16 2018

Form CP-2/3

JAN 08 2018

CONSERVATION DIVISION
WICHITA, KS