

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 266 N. Main St., Ste. 220  
 Wichita, KS 67202-1513

API Well Number: 15-189-21145-00-00  
 Spot: NENENE Sec/Twnshp/Rge: 3-32S-35W  
4931 feet from S Section Line, 330 feet from E Section Line  
 Lease Name: HELMLEY A Well #: 1  
 County: STEVENS Total Vertical Depth: 6225 feet

Operator License No.: 4523  
 Op Name: NUOIL CO., INC.  
 Address: RR 1  
MOSCOW, KS 67592

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5545		WITH 2 SX CMT
CIBP		6000		
PROD	4.5	6223	1780	WITH 300 SX CMT
SURF	8.625	1693		WITH 650 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/16/2018 9:00 AM  
 Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
 Proposal Revd. from: BRIAN KARLIN Company: NUOIL CO. Phone: (785) 623-3290

Proposed Plugging Method: SET CIBP @ 5550' WITH 2 SX CMT ON TOP. PLUG AT 1720' WITH 20 SX GEL & 50 SX CMT. PLUG AT 630' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)  
 Date/Time Plugging Completed: 01/16/2018 3:40 PM KCC Agent: HEITH WALSH

Actual Plugging Report:

SET CIBP @ 5545' WITH 2 SX CMT. PRESSURE TEST CASING TO 300#. DID NOT HOLD. CUT CASING AT 1780' THEN TOOHP WITH CASING. 1ST PLUG AT 1725' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 598' WITH 50 SX CMT. 3RD PLUG AT 32' WITH 20 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
6090	6096		SQZD
6056	6066		
5594	5600		

INVOICE  
FEB 08 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed Heith Walsh  
 (TECHNICIAN)

RECEIVED  
 JAN 18 2018  
 KCC DODGE CITY *MR*

*SW*