

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-21124-00-00  
Spot: SWNWSE Sec/Twnshp/Rge: 9-35S-11E  
1670 feet from S Section Line, 2327 feet from E Section Line  
Lease Name: MEEKS Well #: OW-1  
County: CHAUTAUQUA Total Vertical Depth: 1834 feet

Operator License No.: 4448  
Op Name: PERKINS OIL ENTERPRISES, INC.  
Address: PO BOX 707  
HOWARD, KS 67349

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1834		
SURF	7	97		20 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/18/2017 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: BUDDY FINNEY Company: \_\_\_\_\_ Phone: (620) 505-0479

Proposed Plugging Method: Run 1" to TD 1834 Pump 50' cement plug Pump Gel Spacer; Pull pipe to 700'; Pump 50' cement plug; Pull pipe up to 350' Pump cement to surface; Pull rest of pipe out and top off with cement.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE  
Date/Time Plugging Completed: 12/18/2017 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1160' gelled hole and spotted 5 sack plug. Pulled up to 900' and spotted 5 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 52 sacks of cement were used to plug this well.

RECEIVED  
KCC DIST # 3  
JAN 30 2018  
CHANUTE, KS


INDORGE  
FEB 03 2018

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH THE KCC.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)