

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-047-20356-00-00  
Spot: NWNW Sec/Twnshp/Rge: 29-26S-17W  
4689 feet from S Section Line, 4571 feet from E Section Line  
Lease Name: VOEGELIA Well #: 1  
County: EDWARDS Total Vertical Depth: 4632 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 N MARKET STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4500		WITH 2 SX CMT
PROD	4.5	4632	0	WITH 150 SX CMT
SURF	8.625	285		WITH 225 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/28/2017 2:00 PM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: CIBP @ 4500' WITH 2 SX CMT. PERFORATE AT 1200' WITH 50 SX CMT & 100# HULLS IN LAST 25 SX CMT. PERFORATE AT 320' & TRY TO CIRCULATE INSIDE & OUT. TOP OFF. TIE ONTO 8 5/8" X 4 1/2" & TRY TO PUMP CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/28/2017 4:00 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

CIBP @ 4500' WITH 2 SX CMT ON TOP WITH BAILER. PERFORATE AT 1200' WITH 2 SHOTS, PUMP 50 SX CMT WITH 100# HULLS IN LAST 25 SX CMT THROUGH TBG AT 1200'. PERFORATE AT 320' WITH 2 SHOTS, PUMP 35 SX CMT THROUGH TBG. CIRCULATED CMT TO SURFACE IN 4 1/2" CASING. NO BLOW ON ANNULUS. TIED ONTO 4 1/2" X 8 5/8" ANNULUS & PUMPED 5 SX CMT. PRESSURED TO 150#. SHUT IN WITH BULL PLUG. TIED ONTO 4 1/2" CASING & SQUEEZED 15 SX CMT OUT AT 320'.

Perfs:

Top	Bot	Thru	Comments
4537	4550		

INVOICE  
FEB 08 2018

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed \_\_\_\_\_

*[Signature]*  
SA (TECHNICIAN)

RECEIVED  
JAN - 9 2018  
KCC DODGE CITY *[Signature]*