

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-133-25930-00-00
Spot: NWSENE SW Sec/Twnshp/Rge: 6-30S-18E
1817 feet from S Section Line, 2046 feet from W Section Line
Lease Name: SHANE COLLINS Well #: 1
County: NEOSHO Total Vertical Depth: 1164 feet

Operator License No.: 35341
Op Name: RIVER ROCK OPERATING, LLC
Address: 211 N. ROBINSON SUITE 200
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1150		187 SX
SURF	8.625	20		6 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 12/26/2017 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: JORDAN JAMESON Company: RIVER ROCK OPERATING, LLC Phone: (620) 702-7440

Proposed Plugging Method: Circulate cement from TD to surface through tubing, 10% excess. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Fill pits and reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 12/26/2017 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375 inch cement string was lowered to TD and then 70 sacks of cement with cottonseed hulls were pumped. The cement string was pulled to 800 ft and the well pumped full of cement to surface. The cement string was removed and the well topped off. The wellhead was cut off below plow depth and the location restored. A total of 82 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
766	768		
743	745		
680	684		
664	667		

RECEIVED
KCC DIST # 3
JAN 16 2018
CHANUTE, KS

AD

Remarks:

Plugged through: CSG

INVOICE
FEB 08 2018

District: 03

Signed

Alan M. Dunning
(TECHNICIAN)