

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-133-26093-00-00
Spot: SEWNENE Sec/Twnshp/Rge: 12-30S-18E
2022 feet from S Section Line, 865 feet from E Section Line
Lease Name: FARBER JUDITH M Well #: 12-1
County: NEOSHO Total Vertical Depth: 1037 feet

Operator License No.: 35341
Op Name: RIVER ROCK OPERATING, LLC
Address: 211 N. ROBINSON SUITE 200
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1031		135 SX
SURF	8.625	21		6 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 12/06/2017 1:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: JORDAN JAMESON Company: RIVER ROCK OPERATING, LLC Phone: (620) 432-4200

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/06/2017 1:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375 inch cement string was lowered to TD and then 70 sacks of cement with cottonseed hulls were pumped. The cement string was pulled to 500 ft and the well pumped full of cement to surface. The cement string was removed and the well topped off. The wellhead was cut off below plow depth and the location restored. A total of 112 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
970	974		
910	912		
695	697		
655	658		
542	546		
529	533		

RECEIVED
KCC DIST # 3
JAN 16 2018
CHANUTE, KS

AD

INVOICE
FEB 08 2018

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning
(TECHNICIAN)