

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-125-32087-00-00  
Spot: NWSESWNW Sec/Twnshp/Rge: 3-35S-17E  
2150 feet from N Section Line, 800 feet from W Section Line  
Lease Name: BRADLEY, RICHARD E Well #: 3-2  
County: MONTGOMERY Total Vertical Depth: 1030 feet

Operator License No.: 35341  
Op Name: RIVER ROCK OPERATING, LLC  
Address: 211 N. ROBINSON SUITE 200  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1025		185 SX
SURF	8.625	23		4 SX
T1	1.5	864		

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/08/2017 12:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Revd. from: JORDAN JAMESON Company: \_\_\_\_\_ Phone: (620) 432-4200

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE  
Date/Time Plugging Completed: 12/08/2017 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" to TD and pumped 105 sacks of cement with cottenseed hulls. Pulled up to 500' and circulated cement to surface. Pulled 2" and topped well off. A total of 168 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
692	696		

RECEIVED  
KCC DIST # 3  
JAN 30 2018  
CHANUTE, KS


DS

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

INVOICE  
FEB 08 2018