

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-19372-00-00  
Spot: NWSEWSE Sec/Twnshp/Rge: 10-34S-11E  
1764 feet from S Section Line, 1762 feet from E Section Line  
Lease Name: BELLMON Well #: 2  
County: CHAUTAUQUA Total Vertical Depth: 1150 feet

Operator License No.: 34680  
Op Name: TDOT OIL, INC.  
Address: PO BOX 117  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1150		0 SX
SURF	7	40		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/19/2018 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Revd. from: TIM DOTY Company: \_\_\_\_\_ Phone: (620) 331-9791

Proposed Plugging Method: Plug according to KCC instructions. Cement unknown.

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/22/2018 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1100' gelled hole and spotted 10 sack plug. Pulled 1" out and perforated casing at 600'. Ran 1" back into 600' and spotted 10 sack plug. Pulled 1" and shot casing off at 300'. Pulled casing. Ran 1" back into 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 200 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1085	1095		

RECEIVED  
KCC DIST # 3  
JAN 30 2018  
CHANUTE, KS

DS

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)