

State of Kansas



15-113-00110-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
DEC 13 1966
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Lamb of Alfred Koehn has this

date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Alfred Koehn

Complete Address: Galva, Kansas

Lease Name: Becker Well No. # 1

Location: NE NE NW Sec. 4 Twp. 20 Rge. 1 (E) (W)

County McPherson Total Depth 3607' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lamb was instructed to plug the well as follows:

8 5/8"-187'-Circulated w/cement. 5 1/2"-3055'-Cemented. Plug at 3000'.

Top perforations-2963 1/2". Sand hole to 2955'. 5 Sax.cement 2955' to 2900'

Mud 2900' to 200'. Bridge 200' to 190'. 25 Sax.cement 190' to 115'

Mud 115' to 40'. Bridge 40' to 30'. 10 Sax.cement 30' to 0.

Very truly yours,

[Signature]
Conservation Division Agent