



15.113.20627.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

March 24, 1979

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 27 1979

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Willard Brucker of Blackstone Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Brucker guarantees payment of the plugging fee.

Operator's full Name: Roger A. Schultz

Complete Address: Box 273, Canton, Kansas

Lease Name: Albert Kocher Well No. 1

Location: C W/2 NE Sec. 4 Twp. 20 Rge. 1 (E) (W) X

County: McPherson Total Depth 3015' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Brucker was instructed to plug the well as follows:

Fill hole with mud to 150'. Push plug and 1/2 sack
hulls to 150' and cement hole with 15 sacks
cement. Fill hole with mud to 40'. Push plug and
1/2 sack hulls to 40' and cap hole with 10 sacks cement.
Bridge rathole and cement with 2 sacks cement.
8 3/8" - 154' - cement circulated

Very truly yours,

Conservation Division Agent