



15-113-20713-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

April 28, 1980

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

JOHN CARLIN
R. C. LOUX
JANE T. ROY
WILLIAM G. GRAY
Carol J. Larson, Executive Secretary

Governor
Chairman
Commissioner
Commissioner

RECEIVED
STATE CORPORATION COMMISSION
MAY - 2 1980
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Willard Brucker of Blackstone Drilling, Inc. has
date requested permission to plug the following described well:

Mr. Brucker guarantees payment of the plugging fee.

Operator's full Name: Kermit Schmidt

Complete Address: Rt. 2 - Box 198, Canton, Kansas 67428

Lease Name: Adams-Stevenson Well No. 1

Location: C NE NE SE Sec. 14 Twp. 20 Rge. 2 (E) (W) X


County: McPherson Total Depth 3002' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Brucker was instructed to plug the well as follows:

8 5/8" - 131' - cem. circ. Fill hole with mud to 125'. Push
plug and 1/2 sack hulls to 125' and cement hole with
20 sacks cement. Fill hole with mud to 40'. Push plug
and 1/4 sack hulls to 40' and cap hole with 10 sacks
Cement. Bridge cathod and cement with 2 sacks

Very truly yours,


Conservation Division Agent