

State of Kansas



FORM - CP-2
Rev. 6-26-62

15-113.01655.0000

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 31 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Pat Pouffe of Blackston drlg.Co. has this date requested permission to plug the following described well:

Mr. Pouffe guarantees payment of the plugging fee.

Operator's full Name: George C. Hess

Complete Address: 505 N. Charles St. McPherson, Kansas.

Lease Name: Dan Becker Well No. I

Location: C NL ^{NE} SE Sec. II Twp. 20 Rge. 2 /(E)/(W)

County McPherson Total Depth 2993' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pouffe was instructed to plug the well as follows:

Fill hole w/ 36 vis mud from T.D. 2993' back to 150'. set a plug and
hulls at 150' and run 20 sax cement. Fill hole w/ mud from 80' back to
30' set a plug and 8 sax cement. fill rat hole w/ mud and 2 sax cement.

Very truly yours,

Conservation Division Agent