



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
AUG 4 1975
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Oilfield Supply & Trading Inc.

Complete Address 430 Greenwood Wichita, Kansas 67211

Lease Name Otte Well No. # 1

Location SW SW SW Sec. 33 Twp. 20 Rge. (E) 1 (W)

County McPherson Total Depth 3030'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Dunbar Drilling Inc.

Address Wichita, Kansas License No. # 709

Operation Completed: Hour 2 PM Day 1 Month 8 Year 75

The above well was plugged as follows:

8 5/8"-204'-Circulated w/cement. 5 1/2"-3029'-Cemented. Perf. 3016'.

Sand to 2950'. 10 Sax. Cement. Mud to 260'. Bridge 260' to 250'.

40 Sax. Cement at 250'. Mud to 40'. Bridge 40' to 30'. 10 Sax.

Cement 30' to 0. Pulled 1029' 05 1/2"-Pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed:
Well Plugging Supervisor

DATE 8/5/75

INV. NO. 1718-W