

15.113.30012.0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

037 50 1975
10-30-75
CON. DIVISION
W. LINDA, KANSAS

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name John W. Casebeer Oil & Gas

Complete Address Rt. 1 McPherson, Kansas 67460

Lease Name J. L. Young Well No. # 1

Location NW SW SW Sec. 9 Twp. 20 Rge. (E) 1 (W)

County McPherson Total Depth 3448'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Chase, Kansas License No. # 683

Operation Completed: Hour 4 PM Day 28 Month 10 Year 75

The above well was plugged as follows:

8 5/8"-161'-Circulated w/cement. 5 1/2"-3433'-Cemented. Perf. 2941'.

Sand to 2900'. 5 Sax. Cement. Mud to 190'. Bridge 190' to 180'.

25 Sax. Cement 180'. Mud to 40'. Bridge 40' to 30'. 10 Sax.

Cement 30' to 0. Pulled 1100'-5 1/2"-Pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 10/30/75

INV. NO. 2154-W