

KANSAS

10 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 12 1966

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Alfred Koehn

Complete Address: Galva, Kansas

Lease Name Becker Well No. # 1

Location NE NE NW Sec. 4 Twp. 20 Rge. 1 (E) (W)

County McPherson Total Depth 3607'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Art Lamb Casing Pulling Co.

Address: Hutchinson, Kansas License No. 440

Operation Completed: Hour 4 PM Day 9 Month 12 Year 66

The Above well was plugged as follows:

8 5/8"-187'-Circulated w/cement. 5 1/2"-3055'-Cemented. Plug back to 3000'.

Top Perforations-2963 1/2". Sand hole to 2955'. 5 Sax.cement 2955' to 2900'.

Mud 2900' to 200'. Bridge 200' to 190'. 25 Sax.cement 190' to 115'.

Mud 115' to 40'. Bridge 40' to 30'. 10 Sax.cement 30' to 0.

Pulled 2500'-5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/13/66
INV. NO. 4444-w

Signed: [Signature]
Well Plugging Supervisor