

15.113.30237.0000

Form CP-3
Rev. 6-26-62

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 20 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Rex & Morris Drlg. Co. & T.A.Wells

Complete Address: Box 448, Eldorado, Kansas.

Lease Name Tinsley Well No. I

Location NW NW NW Sec. 5 Twp. 20 Rge. I (W) (W)

County McPherson Total Depth 3046'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co tolls

Address: same License No. Rotary

Operation Completed: Hour 6:PM Day 14 Month 2 Year 63

The Above well was plugged as follows:

Filled hole w/ sand from T.D. 3046' back to 2963' ran 5 sax cement w/ dump bailer.

Shot off and pulled 5 1/2" casing. Filled hole w/ mud from 2930' back to 218' set a

10' rock bridge and ran 20 sax cement from 218' back to 148'. Filled hole w/ mud from

148' back to 30' set a 5' rock bridge and ran 8 sax cement from 30' back to zero.

8/5/8" surface pipe 3' below ground level.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/20/63

INV. NO. 6619-u

Signed: [Signature]
Well Plugging Supervisor