

15-051-02604-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Louis M. Mai Operations

Complete Address: P. O. Box 33 Russell, Kansas

Lease Name Dinkel Well No. 6

Location C S/2 SW Sec. 22 Twp. 13 Rge. 16 (E) (W) X

County Ellis Total Depth 3480'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Co.

Address: Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 4 P Day 24 Month 4 Year 1967

The Above well was plugged as follows:

Total Depth 3480' 8 5/8 csg set at 247' cwc 150 sc.

5 1/2 csg set at 3470' cw 100 sc cement.

5 1/2 csg PB 3460!

5 1/2 csg squeezed at 650' with 250 sc cement.

Poured 10 gal sand at 3460' and dumped 2 sc cement with dump bailer.

Recov. 260' of 5 1/2 csg.

Set plug at 240'--10' rock and 3 yds readymix cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. W. Mansury
Well Plugging Supervisor

DATE 4/26/67

INV. NO. 5117-W