

~~KANSAS~~

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 15 1975 4-15-1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Graham-Michaelis Corporation

Complete Address P.O. Box 247, Wichita, Kansas 67201

Lease Name Barnhart Well No. 1-22

Location NE NE SW Sec. 22 Twp. 20 Rge. 7 (E) (W) X

County Rice Total Depth 3375'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 1 PM Day 10 Month April Year 1975

The above well was plugged as follows:

Hole filled with sand to 3325' and cemented with 5 sacks cement.

Hole filled with mud to 260'. Rock bridge set from 260' to 250' and hole cemented with 25 sacks cement. Hole filled with mud to 40'.

Rock bridge set from 40' to 30' and hole cemented to base of cellar with 10 sacks cement.

2491' of 5 1/2" casing recovered.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 4/15/75

INV. NO. 1175-W