

959

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name George Hess

Complete Address 505 North Charles McPherson, Kansas 67460

Lease Name Otte Well No. 1

Location C SW NW Sec. 21 Twp. 20 Rge. 1 (66) (W)

County McPherson Total Depth 2998'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Art Lamb Casing Pulling

Address hutchinson, Kansas License No. 440

Operation Completed: Hour 7 PM Day 3 Month 6 Year 71

The above well was plugged as follows:

8 5/8"-151'-Circulated w/cement. 5 1/2"-2975'-Cemented. Sand to 2970'.

5 Sax. cement 2970' to 2930'. Mud 2930' to 170'. Bridge 170' to 160'.

25 Sax. cement 160' to 100'. Mud 100' to 40'. Bridge 40' to 30'.

10 Sax. cement 30' to 0. Pulled 2113'-5 1/2"-Pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 6-7-71
INV. NO. 3808-W