

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

McPherson

County. Sec. 21 Twp. 20S Rge. 1W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW NW

Lease Owner M & L Oil Company

Lease Name Otte Well No. 1

Office Address 913 Brwon Bldg. - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 19

Application for plugging filed May 6 19 55

Application for plugging approved May 10 19 55

Plugging commenced May 9 19 55

Plugging completed May 14 19 55

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Raul Durkee

Producing formation Depth to top Bottom Total Depth of Well 3411 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	161'	None
				5-1/2"	3411'	2625'
				Hole was plugged back to 2977'		
				Casing was perforated from 2971' to 2974'.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled the hole with sand from 2977' to 2960' and ran 6 sacks of cement. Pulled part of casing and circulated hole with 60 barrels of pit mud. Pulled rest of casing. Bailed the fluid down to 160', set a 10' rock bridge and ran 15 sacks of cement at 150'. Mudded the hole to 30', set a 10' rock bridge and ran 5 sacks of cement on top. Plugging completed.

STATE CORPORATION COMMISSION

JUNE 1955 6-8-55

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.

Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.

Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight

Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 19th day of May, 19 55

Edward E. Owen Notary Public.

My commission expires May 20, 1957

PLUGGING
MAY SEC 21 T 20 R 1W
BOOK PAGE 117 LINE 16


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- M & L OIL CO.
Farm- Otte No. 1

SEC. 21 T.20 R.1W
NW NW NW

Total Depth. 3004 1/2'
Comm 5-10-54 Comp. 5-17-54
Shot or Treated.
Contractor. Mallard Drilg. Co.
Issued. 7-24-54

County McPherson
KANSAS



CASING:
8 5/8" 161' w/100 sx cem.

Elevation. _____

R.D.B. 5 1/2' fr ground level. Production. Dry
Figures Indicate Bottom of Formations.

Measurements from R.D.B.	
yellow clay	23
sand	69
blue shale	161
shale-lime	435
lime	1035
shale-lime	2130
shale-sand	2330
lime	2620
lime-shale	2960
Mississippi	3004 1/2
Total Depth	

TOPS:
Kansas City 2337

RECEIVED
STATE CORPORATION COMMISSION
JUN 2 - 1955
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 21 T 20 R 1W
BOOK PAGE 112 LINE 16