

RP  
Form CP-4

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Mc Pherson County. Sec. 21 Twp. 20 Rge. 1 W (E) (W)  
Location as "NE/CNWxSWx" or footage from line: C S/W4 NW/4

Lease Owner George Hess  
Lease Name Otte Well No. I  
Office Address 505 North Charles Mc Pherson  
Character of Well (completed as Oil, Gas or Dry Hole) Gas  
Date well completed 4-6 1965  
Application for plugging filed 5-17 1971  
Application for plugging approved 5-18 1971  
Plugging commenced 5-20 1971  
Plugging completed 6-3 1971  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well Hugh Scott  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2998' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2, 113'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged off bottom of hole with sand. Sand from 2998' to 2970'. Dumped 5 sx of cement. Mudded hole to 170'. Made 10' of rock bridge. Dumped 25 sx of cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 9 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Art Lamb Casing Pulling Co.  
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.  
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb  
2809 King St. Hutchinson, Kansas 67501  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of June, 19 71

My commission expires January 5, 1974  
Judy Lamb Notary Public.



**Blackstone Drilling, Inc.**

P. O. BOX 455 . . . PHONE CH 1-1250

McPHERSON . KANSAS

April 7, 1965

COMPANY: HESS & SONS, etal.  
 CONTRACTOR: BLACKSTONE DRILLING, INC.  
 FARM: OTTE #1  
 LOCATION: C-SW/4 NW/4 of Sec. 21-20-1W,  
 McPherson County, Kansas  
 COMMENCED: April 1, 1965  
 COMPLETED: April 6, 1965  
 ELEVATION:

0	to	70	Shale
70	to	90	Sand
90	to	830	Shale & Lime
830	to	1105	Lime & Shale
1105	to	1495	Shale
1495	to	2000	Shale & Lime
2000	to	2165	Lime & Shale
2165	to	2400	Shale & Lime
2400	to	2700	Lime
2700	to	2950	Shale & Lime
2950	to	2995	Lime
2995	to	2998	Mississippi
		2998	T. D.

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 19 1971  
 CONSERVATION DIVISION  
 Wichita, Kansas

Cut 12 1/4 in. hole to 149 ft. and run 151.05 ft. of 8 5/8 in. O.D. casing, cemented on bottom at 149 ft. with 100 sacks cement and 3% Calcium Chloride. Plug down at 10:00 A.M., April 1, 1965. Cut 7 7/8 in. hole to 2998 ft. and run 3002 ft. of 5 1/2 in. O.D. casing and cemented 25 ft. off bottom at 2973 ft. with 30 sacks cement. One sack in rathole. Spotted 25 bbls. of oil and pumped 2 min. Plug down at 2:45 P.M. April 6, 1965.

TOPS: Brown Line - 2271'      Kansas City - 2343'      Mississippi - 2948'

Measurements taken from K.D.

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Otte #1, located on the C-SW/4 NW/4 of Sec. 21-20-1W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.

*H. J. Plouffe*  
 H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 7<sup>th</sup> day of April, 1965.

*Ruth McVay*  
 Ruth McVay - Notary Public

My Commission Expires: December 18, 1965.