

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
809 Bittling Building  
Wichita, Kansas

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging of formations.

NORTH

Section Plat grid for well location

Locate well correctly on above  
Section Plat

McPherson County. Sec. 21 Twp. 20 Rge. (E) 1 (W)  
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NW NE SW  
Lease Owner Aladdin Petroleum Corporation and Crowe Drilling Co.  
Lease Name Boesker Well No. 1  
Office Address 809 Petroleum Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 8 19 51  
Application for plugging filed 10 19 51  
Application for plugging approved 10 19 51  
Plugging commenced 10 19 51  
Plugging completed 18 19 51  
Reason for abandonment of well or producing formation No shows  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Reuel Durkee  
Producing formation Depth to top Bottom Total Depth of Well 3067 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with columns: Formation, Content, From, To, Size, Put In, Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

T.D. to 2960 ft. sand  
2960' to 2930' 6 sax cement  
2930' to 145' Mudded  
145' to 135' Rock Bridge  
135' to 95' 15 sax cement  
95' to 15' Mud  
15' to cellar 5 sax cement

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 27 1951  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Aladdin Petroleum Corporation  
Address 809 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
J. M. JOHNSON (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
described well as filed and that the same are true and correct. So help me God.

(Signature)

Handwritten signature of J. M. Johnson

(Address)

SUBSCRIBED AND SWORN to before me this 11th day of July

Notary Public seal and date AUG 27 1951

My commission expires April 23, 1952

PLUGGING  
FILE SEC 21 T 20 R 44  
BOOK PAGE 89 LINE 9

22-2625 2-48-15M CONSERVATION DIVISION  
Wichita, Kansas

COMPANY: Aladdin Petroleum Corporation and Crowe Drilling Co., Inc.  
 CONTRACTOR: Crowe Drilling Co., Inc.

COMMENCED: April 24, 1951  
 COMPLETED: May 6, 1951 Rotary  
 June 8, 1951 Cable Tools

FARM: Boesker #1  
 LOCATION: NW/c NE/4 SW/4  
 Sec. 21-20S-1W  
 McPherson Co., Ks.

ELEVATION: 1539 D.F.  
 PRODUCTION: D & A

CASING RECORD:  
 8 5/8" Casing set at 148'  
 w/125 sacks of cement  
 5 1/2" Casing set at 3067'  
 G.M. w/75 sacks cement

Pulled 2635' OF 5 1/2"

<u>FORMATION</u>	<u>DEPTH</u>
Top soil, shale, sand & shells	148'
Shale & shells	375'
Lime shells	640'
Lime and shale	890'
Lime, shells & shale	1320'
Shale and shells	1860'
Lime and shale	2120'
Douglas sand	2260'
Lime and shale	2350'
Lime	2710'
Lime and shale	2934'
Lime and chat	2965'
Lime	3073'
 TOTAL DEPTH	 3067' G.M.
 KANSAS CITY	 2333' Gm.
 MISSISSIPPIAN	 2944' Gm.

I hereby certify this to be a true and accurate log of the above described well, as shown by the Daily Drilling Reports.

ALADDIN PETROLEUM CORPORATION

By 

Subscribed and sworn to before me this 11th day of July, 1951

Notary Public.

My commission expires April 23, 1952.

**PLUGGING**  
 FILE SEC 21-20-1W  
 BOOK PAGE 89 LINE 9

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 JUL 27 1951  
 CONSERVATION DIVISION  
 Wichita, Kansas