

Strike out upper line when reporting plugging off formations.

CASING RECORD

[illegible]

Dumped 6 sax cement on bottom; pumped mud in hole to 135' of top. Set wood plug at 135'. Dumped 15 sax of cement and filled hole to top with mud. Cemented base of cellar with 5 sax.

Notary Public.

L O G

DIENER NO. 1, C NE/4 SW/4 of Sec. 1-20S-1W, McPherson County, Kansas

Owner: The Stelbar Oil Corp., et al
Contractor: E. B. ShawverDrilling Commenced: Sept. 17, 1943
Drilling Completed: Oct. 8, 194310 1/4" 100'
5 1/2" O.D. 2900'Elevation:
D. & A.

surface	5
sand	55
shale	532
lime	840
shale	1400
lime	1676
shale	1797
lime	1861
shale	1940
lime	2040
shale sandy	2235
shale	2305
lime	2593
shale	2608
lime	2625
shale	2696
lime	2726
shale	2898
SLM correction	
	2898 = 2893
chat	2925 T.D.

Swabbed 3 bbls. fluid per hr.
in chat, of which 1/2 bbls. was
oil, 2-1/2 bbls. water.