


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

McPherson County. Sec. 29 Twp. 20S Rge. 1 W (W)
Location as "NE/CNW%SW%" or footage from lines NE NE NE
Lease Owner Veeder Supply & Development Co. et al
Lease Name Mabel Jahn Well No. 1
Office Address Box 201, Cherryvale, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 9, 1957 19
Application for plugging filed June 9, 1957 19
Application for plugging approved June 9, 1957 19
Plugging commenced June 9, 1957 19
Plugging completed June 9, 1957 19
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Reul Durkee, McPherson, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3575 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|---------------------|
| | | | | 8 5/8" | 170' | cemented w/115 sks. |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bridge at 160' with 20 sacks cement; heavy mud to 25';
set bridge w/5 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Veeder Supply and Development Co.
Address Box 201, Cherryvale, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.
C. H. Woods (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. H. Woods
Cherryvale, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of June, 19 57

Leo Lawson
Notary Public.

My commission expires July 11, 1960

PLUGGING
FILE SEC 29 T 20 R 1W
BOOK PAGE 19 LINE 16

MAILED
JUN 11 1957
6-15-1957
DIVISION
Cherryvale, Kansas

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Veeder Supply & Development Co. et al Farm Mabel Jahn No. 1 Depth 3575'
 Contractor Veeder Supply & Development Co. Pipe 170' 8 5/8" csg w/115 saks.
 Location NE/4 NE/4 NE/4 Sec 29 Twp. 20S Range 1W
 Commenced 5-25-1957 Completed 6-9-1957 County McPherson State Kansas

| | | | |
|-----------------------|------|------|-----|
| Clay | 0 | 20 | 20 |
| Shale and lime | 20 | 40 | 20 |
| Sand | 40 | 110 | 70 |
| Red rock | 110 | 145 | 35 |
| Lime and shale | 145 | 170 | 25 |
| Shale and lime strks. | 170 | 675 | 505 |
| Lime w/shale strks. | 675 | 950 | 275 |
| Shale | 950 | 1120 | 170 |
| Shale & shells strks. | 1120 | 1475 | 355 |
| Shale w/lime shells | 1475 | 1520 | 45 |
| Shale w/lime strks | 1520 | 1665 | 145 |
| Lime w/shale brks. | 1665 | 1730 | 65 |
| Shale and lime | 1730 | 1845 | 115 |
| Lime and shale brks. | 1845 | 1880 | 35 |
| Lime | 1880 | 1910 | 30 |
| Lime and shale | 1910 | 2123 | 213 |
| Shale, sandy | 2123 | 2148 | 25 |
| Shale | 2148 | 2178 | 30 |
| Shale w/lime strks. | 2178 | 2196 | 18 |
| Sand | 2196 | 2284 | 88 |
| Lime | 2284 | 2310 | 26 |
| Lime and shale | 2310 | 2370 | 60 |
| Lime w/shale brks. | 2370 | 2565 | 195 |
| Lime and shale | 2565 | 2627 | 62 |
| Shale w/lime strks | 2627 | 2660 | 33 |
| Shale and lime | 2660 | 2843 | 183 |
| Shale w/lime straks | 2843 | 2906 | 63 |
| Lime | 2906 | 2946 | 40 |
| Lime Miss. | 2946 | 3126 | 180 |
| Lime & Chert. Miss. | 3126 | 3140 | 14 |
| Lime | 3140 | 3244 | 104 |
| Shale | 3244 | 3445 | 201 |
| Lime, Viola | 3445 | 3450 | 5 |
| Lime | 3450 | 3480 | 30 |
| Simpson Sand | 3480 | 3518 | 38 |
| Sand and shale | 3518 | 3538 | 20 |
| Simpson | 3538 | 3553 | 15 |
| Arbuckle | 3553 | 3575 | 22 |
| T. D. | 3575 | | |

| | |
|------------------|------|
| TOPS: | |
| Mississippian | 2948 |
| Kinderhook | 3244 |
| Mizener | 3414 |
| Viola | 3445 |
| Simpson Dolomite | 3480 |
| Simpson | 3490 |
| Arbuckle | 3554 |

Elevation: 1546 DR. Fl.
1541 Gr.

2948
1546
1402

Dry and abandoned.

AFFIDAVIT

STATE OF KANSAS)
Montgomery County) SS

C. H. Woods, of lawful age, being first duly sworn on oath, deposes and says:

That he has read the above drilling log covering the Mabel Jahn #1 well located in Section 29-20S-1W. McPherson County, Kansas, and that the same is true and correct. Further affiant saith not.

THE VEEDER SUPPLY & DEVELOPMENT CO.
BY C. H. Woods
C. H. Woods

Subscribed and sworn to before me this 11th day of June, 1957.

Robert Lawson
STATE CORPORATE NOTARY PUBLIC
COMMISSION

My commission expires July 11, 1960.

PLUGGING
FILE SEC 29 T. 20 R. 1W
BOOK PAGE 19 LINE 16

JUN 17 1957
CON DIVISION