

15.185.12652.0000

Name: **GROW #1**  
 Location: **SE SE NW section 14-218-12W, Stafford County, Kansas**  
 Company: **Virginia Drilling Company, Inc. and E. H. Adair**  
 Contractor: **Virginia Drilling Company, Inc.**  
 Commenced: **March 5, 1947**  
 Completed: **May 24, 1947**  
 Total Depth: **3580 1/2**  
 Elevation: **1857**

FORMATION	DEPTH	TOPS	
Sand	0-230		
Shale	230-307	Lansing KC	3229
Red shale & shells	307-430	Conglomerate	3474
Red shale & shells	430-620	viola chert	3480
Anhydrite	620-650	Simpson	3503
Shale & shells	650-1075	Arbuckle	3539
salt-shells	1075-1230		
salt-shale	1230-1380		
Shale-lime	1380-1490		
Lime	1490-1645		
Lime, sand - shale	1645-1740		
Lime-sandy	1740-1915		
Lime-shale	1915-1995		
Shale-lime	1995-2175		
Shale	2175-2265		
Shale-lime	2265-2365		
Shale-shells	2365-2460		
Shale	2460-2550		
Lime	2550-2610		
Lime-shale	2610-2715		
Lime-broken	2715-2805		
Lime-rough	2805-2875		
Lime	2875-3005		
Lime-rough	3005-3070		
Lime	3070-3110		
Lime-shale	3110-3185		
Shale	3185-3208		
Lime	3208-3229		
Lime-white	3229-3260		
Lime	3260-3475		
Cherty conglomerate	3474-3504		
Shale	3504-3539		
Arbuckle	3539-3580 1/2		

set 8 5/8" csg. @ 307  
 set 5 1/2" @ 3541.6"

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 14 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

Now comes S. A. Murphy, who states that he is familiar with the drilling of oil and gas wells and known of his own knowledge that the well #1 located in the SE SE NW section 14-218-12W, Stafford County, Kansas, was drilled to a total depth of 3580 1/2 feet, oil being found in the gilleccus lime.

*S. A. Murphy*

subscribed and sworn to before me, a Notary Public, this 23 day of June, 1947.

*Muske*

My commission expires, February 5, 1949.