

WELL LOG HUFFORD 'A' #4

Petroleum, Inc., Lease Owner

Section 28, Twp. 21S, Rge. 13W

Garvey Oil, Contractor

Location: SW NE NW

Rotary Total Depth: 3734

County: Stafford, Kansas

Commenced: November 11, 1950

Production: Arbuckle

Completed: November 22, 1950

Elevation: 1900 D.F.

Casing: 202' of 8 5/8"
3756.28' of 5 1/2"

Figures below indicate bottom of formations:

10	Cellar	3605	Lime & Shale
20	Surface Soil	3650	Viola
108	Sand & Clay	3652	Simpson
202	Shale & Shells	2693	Arbuckle
340	Sand	3734	Lime
380	Shale		
395	Sand	3734	R.T.D.
762	Red Bed		
783	Anhydrite		<u>Tops</u>
815	Shale & Shells		
1645	Shale & Lime	3219	Heebner
2005	Br. Lime	3238	Toronto
2145	Lime & Shale	3253	Base Oread
2305	Shale & Shells	3346	Br. Lime
2715	Lime & Shale	3359	Lensing
2851	Shale & Shells	3574	B.K.C.
2990	Shale & Lime	3616	Viola
3125	Lime	3649	Simpson
3150	Sandy Lime	3684	Arbuckle
3173	Lime & Shale		
3352	Br. Lime		
3372	Lime		

DST #1 3372-92 open 30 mins., closed 15 mins.,
rec. 8' mud.DST #2 3490-3532 open 1 hr., closed 15 mins.,
rec. 70' of oil cut mud, 180' of
oil cut mud and water, & 120' sl. muddy wtgI hereby certify that this is a true and correct log of the above
mentioned well.

PETROLEUM, INC.

STATE OF KANSAS)

) SS.

SEDGWICK COUNTY)


Eric H. Jager
Subscribed to and sworn to before me, a Notary Public in said County
and State this 27th day of November, 1950.

Charlotte Widman
Notary Public

My commission expires: 10-13-54