

9-15

1 040163

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-21,286-0000

C SW NW, SEC. 30, T 20 S, R 20 W/R

3300 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3536

Lease Name Beltz Well # 1

Operator: Ramco Oil & Gas Corporation

County Pawnee 145.93

Name & Address P.O. Box 99

Well Total Depth 4490 feet

Belpre, Ohio 45714

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Company License Number 5418

Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 7:30 p.m. Day: 15 Month: 9 Year: 19 88

Plugging proposal received from Craig Christopher

(company name) Allen Drilling Company (phone) 316-793-5681
Elevation 2210'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1401-29'

1st plug at 1430' with 50 sx cement, 2nd plug at 715' with 50 sx cement,

3rd plug at 320' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:15 p.m. Day: 15 Month: 9 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1430' with 50 sx cement,

2nd plug at 715' with 50 sx cement,

3rd plug at 320' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1988

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

DATE 9-28-88

INV. NO. 22K29

Signed Stephen P. Pfeifer
(TECHNICIAN)