

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW-NW-NW

SEC. 3 TWP. 20 RGE. 16

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Kay

Operator Harms & Knight Address G. Bend-Kansas

Field _____ County Rawlins

Total Depth 3775 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 8 1/2 - 1036 ft. Circulated with cement
5 1/2 casing set at 3734 ft. Plugged back from
bottom to 3730 ft with chat - 6 sacks of cement
dumped at 3730 ft - Shot off & pulled the
5 1/2 casing - Filled with mud to 255 ft. Set Rock
Bridge & 15 sacks of cement at 255 ft. Mud to
30 ft Bridge & 10 sacks of cement at the surface*

RECEIVED

Conservation Div.

C. D. Stough

District Conservation Agent

Date 8-22-49

PLUGGING
FILE SEC 3 T20 R 316
BOOK PAGE 111 LINE 7

AUG 26 1949
CORPORATION
COMMISSION
KANSAS