

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SW-NE-NW

SEC. 8 TWP. 20 RGE. 16 W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Rutherford

Operator M. Haber Oil Corp Address Box #8 - Pratt - Kans

Field \_\_\_\_\_ County Pawnee

Total Depth 3819 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 1119 ft - Circulated with Cement  
5/8 casing set at 3817 ft & cemented - Mixed 5 sacks  
& cement on bottom of hole - Shot off & pulled 290 ft  
of 5/8 casing - Filled with mud to 1100 ft - Bridge &  
15 sacks of cement - Mud to 200 ft - Bridge & 15 sacks  
of cement - Mud to 30 ft - Plug & 12 sacks Cement  
J. Ferris - Pipe Pulling - Contractor

C. M. Stough  
District Conservation Agent

Date 6 - 27 - 48

PLUGGING  
FILE NO. 8-20-160  
BOOK PAGE 40-47

6-30-48

f