


15.145.20079.0000

Form CP-3  
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 4 - 1968

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Appleton Oil Company

Complete Address: 506 Beacon Bldg., Tulsa, Okla.

Lease Name Stump Well No. 1

Location SW NE SW Sec. 8 Twp. 20 Rge. 16 (E) (W) X

County Pawnee Total Depth 1628

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Sage Drlg.

Address: Wichita, Kansas License No.     

Operation Completed: Hour 8A Day 2 Month 10 Year 1968

The Above well was plugged as follows:

RTD 1628' 8 5/8 csg set at 330' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 50 sc cmt.

thru drill pipe. Heavy mud to 300' set cementing plug and displaced 25 sc cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cmt to base

of cellar. Plugged rat hole with 2 sc cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Prof. Massey  
Well Plugging Supervisor

DATE 10/4/68

INV. NO. 8575-W