

15.145.30091.0000

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

JUN -1 1966

Operator's Full Name Robinowitz Oil Co. CONSERVATION DIVISION  
WICHITA, KANSAS  
Complete Address: 1322 E. 50 th. , Tulsa, Okla.  
Lease Name Stump Well No. 1  
Location SW - SW - SW Sec. 8 Twp. 20 Rge. 16 (E) (W) X  
County Pawnee Total Depth 3895  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated:       
Plugging Contractor: B - B drilling Co.  
Address: Wichita, Kansas. License No.       
Operation Completed: Hour 1<sup>00</sup> Day 31 Month 5 Year 1966

The Above well was plugged as follows:

RTD 3895 Ft. 8 5/8 set at 299 Ft. cw 200 sq. circ.  
Filled hole with heavy mud. Set cementing plug at ~~299~~<sup>480</sup> Ft. and displaced  
25 sax cement thru drill pipe. Heavy mud to 290 Ft. set cementing plug  
and displaced 20 sax cement thru drill pipe. Heavy mud to 40 Ft. set ~~solid~~  
bridge of cementing plug, 1 / 3 sax hulls and 10 sax cement to base of cellar.  
Plugged rat hole with 2 sax cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 6/1/66  
INV. NO. 3322-4