

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Appleton Oil Company

Complete Address: 506 Beacon Bldg., Tulsa, Oklahoma

Lease Name Hagerman Well No. 1

Location NE NE NW Sec. 7 Twp. 20 Rge. 16 (E) (W) X

County Pawnee Total Depth 3884'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Garvey Drlg.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 3:30 P Day 24 Month 7 Year 1968

The Above well was plugged as follows:

RTD 3884' 8 5/8 csg set at 321' cwc. Cem. Mat. 100 sc 50-50 poz cem. W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 480' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Rust M. Massey
Well Plugging Supervisor

DATE 7/29/68
INV. NO. 8199-u