

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 26 1975
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Emphasis Oil Operations

Complete Address P. O. Box 506, Russell, Kansas 67665

Lease Name Russell Well No. 1

Location 150' N of NW SE NE Sec. 7 Twp. 20 Rge. (E) (W) 16

County Pawnee Total Depth 3942'

Abandoned Oil Well Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405, Chase, Kansas 67524 License No. 436

Operation Completed: Hour 2:30 P Day 24 Month 11 Year 1975

The above well was plugged as follows:

Total Depth 3942' 8 5/8 csg set 248' cwc 150 sk.

5 1/2 csg set 3808' cw 50 sk cmt.

Set 5 1/2 wood plug at 3750' -poured 20' sd -dumped 5 sk cmt W/dump bailer. (3750-3700)

Cutoff & recovered 2360' of 5 1/2 csg.

Mixed & pumped down 8 5/8 csg with 25 sk gel & water W/100 lbs hulls, plug &

120 sk 50-50 poz 2% total gel by Allied Cementing Co. PP 450 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 11-26-75

INV. NO. 2812-L