

R

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

RECEIVED
STATE CORPORATION COMMISSION

APR 27 1977 (well)

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Kinderkook Oil & Gas

Complete Address 4608 Blvd Place, Des Moines, Iowa 50311

Lease Name C. E. Antenen Well No. 1

Location 150' S of SW NE Sec. 6 Twp. 19 Rge. (E) (W) 24

County Ness Total Depth 4422'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Pipe Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 1 P Day 26 Month 4 Year 1977

The above well was plugged as follows:

Total Depth 4422' 8 5/8 csg set 280' cwc 180 sx.

4 1/2 csg set 4371' cw 100 sx cem.

Filled 4 1/2 csg W/sd (4422'-4350') dumped 3 sk cem W/dump bailer. (4350'-4320')

Cutoff & recovered A/3800' of 4 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water -70 sx

50-50 poz 6% -displaced with 5 sk gel & water & capped with wood plug & 70 sk

50-50 poz 6% & shutin. MPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 4-28-77

INV. NO. 5047-W