

KANSAS

74

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 30 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name McClure Oil Company

Complete Address: 1301 Plaza Bldg, Wichita, Kansas

Lease Name Antenem Well No. 1

Location C NE NE Sec. 6 Twp. 19 Rge. 24 (E) (W) X

County Ness Total Depth 4440'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: OWWO

Plugging Contractor: Leben Drlg. Inc.

Address: Wichita, Kansas License No.

Operation Completed: Hour 11:30 PDay 25 Month 10 Year 1967

The Above well was plugged as follows:

RTD 404' 4440' 8 5/8 csg set at 404' cwc.

Gunned 4 pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 390' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 10/30/67
INV. NO. 6576-w