

*JK*  
KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT  
RECEIVED  
SEP 23 1974

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Mull Drilling Company, Incorporated,

Complete Address 415 Page Court, 220 West Douglas, Wichita, Kansas.

Lease Name Antenen Well No. A-1

Location CSE-NE Sec. 6 Twp. 19 Rge. (E) (W)24

County Ness Total Depth 4417'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Rockhold Engineering, Incorporated,

Address Box #698, Great Bend, Kansas. License No. 690

Operation Completed: Hour 2:30 PM Day 19 Month 9 Year 1974

The above well was plugged as follows:

248'--8 5/8" Surface casing, cement circulated with 200 Sx.  
4353'--4 1/2" Production casing cemented with 100 Sx. Well plugged back to 4321'. Top  
of perforations @ 4289'.

Pushed plug to 4250', sanded back to 4225' and set 4 Sx. cement with dump bailer.

Pulled 4 1/2" casing (2500') and squeezed well initially with 5 sacks hulls and 13 sacks  
gel, followed with 65 Sx. cement (6% gel) from 900' to 600' then 8 sacks gel from  
600' to 275' and followed with 25 Sx. cement from 275' to 200' then 4 sacks gel from  
200' to 40' and finally 10 Sx. cement from 40' to bottom of cellar. Maximum pump-in  
pressure-900#. FSIP-350#. (Mudding And Cementing by Allied Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 9/23/74  
INV. NO. 9936-W