

15.135.20888.00.00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 20 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling, Inc.

Complete Address Box 18407 Wichita, Kansas 67208

Lease Name Stum "C" Well No. 1

Location C SW SE. Sec. 31 Twp. 19 Rge. (E) (W) 23

County Ness Total Depth 4382

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 2:45 P Day 18 Month 12 Year 1974

The above well was plugged as follows:

Total Depth 4382' 8 5/8 csg set at 352' cwc 200 sx.

5 1/2 csg set at 4370' cw 100 sx cem.

Filled 5 1/2 csg W/sd (4382-4350) dumped 4 sk cem W/dump bailer. (4350-5320)

Cutoff & recovered 3012' of 5 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water W/300 lbs hulls -released 8 5/8 plug

& pumped 80 sk cem. -displaced with 15 bbl water & capped with 20 sk cem.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/24/74

INV. NO. 523-W

Signed: Leo F. Mearns
Well Plugging Supervisor