

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENCY'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1977 12-21-77
CONSERVATION DIVISION
Wichita, Kansas
(Office of this well)

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

Operator's Full Name The Maurice L. Brown Co.

Complete Address 200 Sutton Place, Wichita, Kansas 67202

Lease Name F. Rein Well No. 1

Location C SE NE Sec. 28²⁹ Twp. 19 Rge. (E) (W) 21

County Ness Total Depth 4520'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering

Address Box 698, Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 3 P Day 20 Month 12 Year 1977

The above well was plugged as follows:

Total Depth 4520' 8 5/8 csg set 550' cwc 250 sk.

5 1/2 csg set 4510' cw 150 sk.

5 1/2 csg PBDT 4451' with top perf. (4418')

Filled 5 1/2 csg W/sd (4451'-4400') dumped 5 sk cem W/dump bailer. (4400'-4365')

Cutoff & recovered 3200' of 5 1/2 csg.

Halliburton Cementing Co. mixed & pumped down 8 5/8 csg with 15 sk gel & water

W/100 lbs hulls, released cementing plug & pumped 130 sk "Halliburton-Light"

& shutin. SIP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo Masonry
Well Plugging Supervisor

INVOICED

DATE 12-21-77

INV. NO. 6427-W