

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Alpine Oil & Royalty Co.

Complete Address: 800 Bitting Bldg., Wichita, Kansas

Lease Name Stieben Well No. 1

Location C NE SE Sec. 8 Twp. 19 Rge. 21 (E) (W) XX

County Ness Total Depth 4400'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: Gabbert - Jones Drlg.

Address: Wichita, Kansas License No.     

Operation Completed: Hour 9:30P Day 12 Month 10 Year 1968

The Above well was plugged as follows:

RTD 4400' 8 5/8 csg set at 323' cwc. Cmt Mat 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sc cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 10/14/68  
INV. NO. 8632-U

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 14 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: Leo F. Massey  
Well Plugging Supervisor