

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

FEB 5 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Davis Bros

Complete Address: 510 Mc Farlin Bldg Tulsa, Okla

Lease Name Continental Well No. 1

Location CSW SE Sec. 18 Twp. 18 Rge. (E) (W) 25  
26

County Ness Total Depth 4549

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A x

Other well as hereafter indicated:     

Plugging Contractor: Terrel Drg Co

Address: Russell, Kansas License No.     

Operation Completed: Hour 11AM Day 2 Month 2 Year 62 63

The Above well was plugged as follows:

8 5/8" 155' circulated with cement.

Circulated hole with heavy mud, set cementing plug at 700', displaced 20  
sax cement through drill pipe, heavy mud to 180', set plug and displaced 20  
sax cement through drill pipe, heavy mud to 40', set plug, 1/2 sack hulls  
and filled to bottom cellar with cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edon [Signature]  
Well-Plugging Supervisor

DATE 2/5/63

INV. NO. 6533-W