

15.135.30078.00.00

Form CP-3
Rev. 6-26-62

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 7 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Slawson Drg Co
Complete Address: 408 One Twenty Bldg Wichita, Kans
Lease Name Elmore Well No. E-1
Location CSE SE Sec. 8 Twp. 18 Rge. (E) (W) 25
County Ness Total Depth 4428
Abandoned Oil Well Gas Well Input Well SWD Well D & A x
Other well as hereafter indicated:
Plugging Contractor: same & Sun Cementing Co
Address: License No.
Operation Completed: Hour 9PM Day 3 Month 9 Year 65

The Above well was plugged as follows:

8 5/8" 303' circulated with cement.
Circulated hole with heavy mud, set plug at 600', displaced 20 sax
cement through drill pipe, heavy mud to 240', set plug, and displaced
20 sax cement through drill pipe, heavy mud to 40', set plug, hulls and
filled to bottom cellar with cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Eldon P. ...*
Well Plugging Supervisor

DATE 9/8/65
INV. NO. 1769-W