

20
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

4-1-66

RECEIVED
STATE CORPORATION COMMISSION

APR 1 1966

Conservation Division
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Mack Oil Co.

Complete Address: 812 Union Center Wichita, Kansas

Lease Name Schuler "B" Well No. 1

Location C-SE-NW Sec. 14 Twp. 18 Rge. 24 (E) (W) X

County Ness Total Depth 4413

Abandoned Oil Well ^ Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Inc.

Address: Chase Kansas License No. 436

Operation Completed: Hour 10 A Day 31 Month MAR. Year 1966

The Above well was plugged as follows:

f.i.d. 4413 8 5/8 at 282' (CWC) 225 SAx. 4 1/2 at 4413' CW 7 1/2 SAx

D.V. tool at 998' CW 225 SAx. Perf. at 4340'

Sand to 4330 - and 45 SAx cement with Dump Bailer.

Bridge at 325' - 104t. Rock & 10 SAx cement. Mud to 218" Bridge -

104t. Rock & 10 SAx cem. Mud to 40' - Bridge Plug 107t. Rock

and 10 SAx Cem. to base of Cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo Massey
Well Plugging Supervisor

DATE 4/1/66

INV. NO. 2991-W