

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor  
MARION BEATTY Chairman  
HARRY G. WILES Commissioner  
RICHARD C. BYRD Commissioner  
RAYMOND B. HARVEY Secretary  
CLYDE E. MILLIGAN Counsel

ED  
COMMISSION  
JUL 9 1959  
CONSERVATION DIVISION  
Wichita, Kansas  
7-9-59

Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

I have this date 6-18, 1959, authorized the following plugging operation:

Operator's Full Name: Barnett Moly Co

Complete Address: First Natl Bldg. Wichita Kans.

Lease Name: Mishler Well No. 1

Location: C-Sw-Ne Sec. 22 Twp. 17 Rge. 24 (E) (W)

County: Ness Co. Total Depth: 4578

Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: Any Hole

Operator was instructed to plug well as follows:

Gun pits circulate hole with heavy mud, set cementing plug at 600 ft.  
and displace 20 sac cement thru drill pipe, heavy mud to 200 Ft.  
set cementing plug and displace 15 sac cement, heavy mud to 40 Ft.  
set and tie cementing plug in place, dump 1/2 sac hulls, and displace  
10 sac cement cementing to base of cellar.

Very truly yours, Gilbert P. Leiker

Signed: Gilbert P. Leiker  
Conservation Division Agent