

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 18 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Zorgar Oil Co.

Complete Address 706 Union Nat. Bldg. Wichita Ks.

Lease Name No 11 Well No. B-1

Location C-SE-SE Sec. 16 Twp. 17 Rge. 24 (W)

County Ness Total Depth 4490

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Rains & Williamson Drlg. Co. Inc.

Address 435 Page Ct. Wichita Ks. License No. _____

Operation Completed: Hour 6:15 AM Day 15 Month 9 Year 1974

The above well was plugged as follows:

map sea level Dakota Top +2000 K.B. Elev. +2440

8 5/8" @ 325' cwc 175 sacks.

pumped down Drill Stem.

70 sacks cement 50/50 portmix 6% Gel @ 650'

20 " " " " " @ 320'

Dumped 1/2 sack Halls & pushed wooden plug to 40'

Filled to cellar w/ 10 sacks cement 50/50 portmix 6% Gel.

Allied pump truck.

I hereby certify that the above well was plugged as herein stated.

Signed: Walter Bachman
Well Plugging Supervisor

INVOICED

DATE 9/18/74
INV. NO. 9905-W