

15.135.00450.00.00

Form CP-3
Rev. 6-26-62

W
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
NOV 12 1962
CONSERVATION DIVISION
Wichita, Kansas
11-12-62

Operator's Full Name Petroleum Inc

Complete Address: R R # 2 Great Bend, Kansas

Lease Name Anderson Well No. 1

Location CSF NW Sec. 15 Twp. 17 Rge. (E) (W) 21

County Ness Total Depth 4300

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Rains & Williamson

Address: Wichita, Kans License No. _____

Operation Completed: Hour 7PM Day 7 Month 11 Year 62

The Above well was plugged as follows:

8 5/8" 244' circulated with cement.

Circulated hole with heavy mud, set plug at 550', displaced 20 sax
cement through drill pipe at 550', heavy mud to 180', set plug and
20 sax cement, heavy mud to 35', set plug and 10 sax cement to bottom
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 11/12/62

INV. NO. 5999-w