

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-057-20203-00-01
Spot: SWSE Sec/Twnshp/Rge: 9-29S-22W
665 feet from S Section Line, 1952 feet from E Section Line
Lease Name: WILLIAMS Well #: 9-15
County: FORD Total Vertical Depth: 6983 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 8100 E. 22ND ST. N., BLDG 1900
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6228		WITH 2 SX CMT
PROD	5.5	6272	3288	WITH 125 SX CMT
SURF	8.625	1158		WITH 600 SX CMT

Well Type: SWD UIC Docket No: D31354.0 Date/Time to Plug: 01/09/2018 1:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 6230' WITH 2 SX CMT. PLUG AT 1560' WITH 12 SX GEL & 30 SX CMT. PLUG AT 1200' WITH 50 SX CMT. PLUG AT 450' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/09/2018 2:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

SET CIBP @ 6228' WITH 2 SX CMT. 1ST PLUG AT 1558' WITH 12 SX GEL & 30 SX CMT. 2ND PLUG AT 1210' WITH 50 SX CMT. 3RD PLUG AT 436' WITH 40 SX CMT. 4TH PLUG AT 62' WITH 25 SX CMT. CMT CIRCULATED.

Top	Bot	Thru	Comments
6272	6938	OH	

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: TBG

INVOICED
FEB 08 2018

District: 01

Signed



(TECHNICIAN)

SA

RECEIVED
JAN 10 2018
KCC DODGE CITY

