

5 020178

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-113-21,152

App SE NW SW, SEC. 28, T. 20 S, R. 4 (W)E

1875 feet from N(S) section line

4375 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4396

Lease Name Smith Well # 1

Operator: Glenwil Energy Corporation
Name & Address 4605 Post Oak Place, Ste. 211
Houston, Texas 77027

County McPherson # 128.38

Well Total Depth 3950 feet

Conductor Pipe: Size 12 3/4 feet 210

Surface Casing: Size 8 5/8 feet 614 210

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Blackstone Drilling, Inc. License Number 5927 Rq #360

Address Box 1184, McPherson, Kansas 67460

Company to plug at: Hour: 6:00 PM Day: 6 Month: July Year: 1985

Plugging proposal received from Brian Galle

(company name) Blackstone Drilling, Inc. (phone) 316 345 8785

were: Fill hole with heavy mud. Pump 35 sacks 60/40 Pozmix w/2% gel through drill pipe @ 3900'. Fill hole. Pump 35 sacks 60/40 Pozmix w/2% gel through drill pipe @ 660'. Fill hole. Pump 25 sacks 60/40 Pozmix w/2% gel through drill pipe @ 215'. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks Cement. Cement yathole with 10 sacks Cement through pipe. Plugging Proposal Received by [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 9:30 PM Day: 6 Month: July Year: 1985

ACTUAL PLUGGING REPORT Hole Filled with mud. 35 sacks 60/40 Pozmix w/2% gel pumped through drill pipe @ 3900'. Filled hole. 35 sacks 60/40 Pozmix w/2% gel pumped through drill pipe @ 660'. Filled hole. 25 sacks 60/40 Pozmix w/2% gel pumped through drill pipe @ 215'. Hole Filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of celler with 10 sacks Pozmix. Pathole cemented with 10 sacks Cement.

Remarks: _____

RECEIVED

For additional description of well, use BACK of this form.)

INVOICED

I (did / did not) observe this plugging on JULY 10 1985

DATE 7-18-85

Signed [Signature] (TECHNICIAN)

INV. NO. 8968

CONSERVATION DIVISION
Wichita, Kansas

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 6-27-85
month day year

API Number 15- 113-21,152

OPERATOR: License # 4396 SE NW 32/4 Sec 28, Twp 20J S, Rge 4E. East West
Name: Glenval Energy Corporation (location)
Address: 4805 Post Oak Place Sui. 211
City/State/Zip: Houston, Texas 77027
Contact Person: [REDACTED]
Phone: (713) 627-7555

RECEIVED
KCG-KDHE

JUN 26 1985

CONTRACTOR: License # 5927
Name: Blackstone Drilling Inc.
City/State: Wichita, Kansas

JOINT OFFICE #5
Salina, KS

Nearest lease or unit boundary line 330 feet.
County: McPherson
Lease Name: Smith Well# 1

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

If OWWO: old well info as follows:
Operator: Conductor 200' 12 3/4" 6/28/85
Well Name: S.P. 600' 8 5/8"
Comp Date: 5-1-85
Projected Total Depth: 3900 feet
Projected Formation at TD: Miss.
Expected Producing Formations: Sun. A.R.B.

Depth to Bottom of fresh water 20 ~ 120 feet
Lowest usable water formation
Depth to Bottom of usable water 200 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 200 feet
Conductor pipe if any required 200 feet
Ground surface elevation 1482 feet MSL.
This Authorization Expires 12-25-85
Approved By [Signature]

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date: 6-25-85 Signature of Operator or Agent: [Signature] Title: Independent Geologist
RCH for KDHE