

5 030521

8-16

113-20,974-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

SW NE NE, SEC. 14, T 20 S, R 83 W/EX

4620 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4424

Lease Name Reichert-Farms Well # "A" 5

Operator: Smokey Valley Resources

County McPherson 98.87

Name & Address P. O. Box 165

Well Total Depth 3042 feet

McPherson, KS 67460

Conductor Pipe: Size feet

Surface Casing: Size 8-5/8 feet 205' w/165 sx

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: pm Day: 8 Month: 8 Year: 1989

Plugging proposal received from Vernon Dunce

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4-1/2" @ 3042 w/75 sx - sand to 2980 - cap w/4 sx - recover available

pipe - Perf 3028' to 3032' - call for top.

RECEIVED
STATE CORPORATION COMMISSION
STATE OF KANSAS

(3 hulls, 15 gel, 100 60/40 poz 4% gel)

AUG 29 1989

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dist #2 (TECHNICIAN)

Plugging Operations attended by Agent?: All Part top None

Operations Completed: Hour: 11:20 Day: 16 Month: 8 Year: 1989

ACTUAL PLUGGING REPORT Plugged back w/sand to 2975 - capped w/4 sx by bailer -

recovered 29 jts 4-1/2" casing approx 1200' - mixed 150# hulls w/15 sx gel -

plugged 8-5/8" followed w/150 # hulls in approx 100 sx 60/40 poz 4% gel -

MAX PSI 700# - SHUT IN 300# (8/17/89 - O.K., 5' from bottom of cellar)

Remarks: Allied #5752
(If additional description is necessary, use BACK of this form.)

INVOICED

did not observe this plugging.

DATE 8-31-89

WC

Signed Merlan Lurah (TECHNICIAN)

INV. NO. 25975